



**NOTES:**

1. PRE-CUT EXP. JOINT MATERIAL SHALL BE USED IN ALL EXPANSION JOINTS.
2. CONTRACTION (DUMMY) JOINTS SHALL BE INSTALLED AT 10' INTERVALS (MAX.)
3. EXPANSION JOINTS SHALL BE INSTALLED AT 40' INTERVALS (MAX.)
4. EXPANSION JOINTS SHALL BE INSTALLED AT THE 'END' OF RADIUS.
5. EXPANSION JOINTS SHALL BE LOCATED A MINIMUM OF 5' FROM INLET STRUCTURES.
6. CONCRETE TO BE CLASS 'A' 3,500 PSI (MIN.)



ENGINEERING DEPARTMENT

6-18 CURB & GUTTER (MODIFIED)

DRAWN: MLC

DATE: 06.07.23

CHECKED: JDB

REVISED: \_\_\_\_\_

APPROVED: EWS

SCALE: NTS